

Blade Exit Angle Effects on Performance of a Standard Industrial Centrifugal Oil Pump

Wen-Guang LI

Department of Fluid Machinery, Lanzhou University of Technology
278 Langongping Road, 730050 Lanzhou, P R China

Email: Liwg38@yahoo.com.cn

ABSTRACT

The effects of blade discharge angle on the performance of a standard industrial centrifugal oil pump of type 65Y60 were investigated experimentally as the pump handled both water and viscous oil. A one-dimensional hydraulic loss model was established to identify such effect mathematically. The effect has been estimated analytically by using the model at various viscosities. The results showed that the blade discharge angle has significant but equal influence on the head, shaft power and efficiency of the centrifugal oil pump at various viscosity conditions. For any viscosity, the total hydraulic loss in the impeller and volute rises with increasing blade exit angle. The diffusion loss in and behind the impellers as well as the friction loss in the volute are noticed in the pump, especially for highly viscous liquids. The hydraulic loss in the impellers is about 0.8-0.6 times the loss in the impellers. In order to improve the pump performance, the hydraulic loss in the volute must be kept as small as possible.

Keywords: centrifugal pump, centrifugal oil pump, performance, blade angle, hydraulic loss, disk friction loss

NOMENCLATURE

b_1	width of blade inlet	Q_t	theoretical flow rate through impeller
b_2	width of blade outlet	Q_w	flow rate of water
b_3	width of volute	Re	Reynolds number
C_M	torque coefficient due to disc friction	Re_2	impeller disc Reynolds number
D_1	diameter of blade inlet	Re_d	Reynolds number in nozzle
D_2	diameter of blade outlet	R_w	radius of wear-rings on impeller
D_3	diameter of circle tangential to volute tongue tip	S_{u2}	tangential blade thickness at outlet
D_8	equivalent diameter of volute throat	t	distance between casing and impeller shroud or hub
D_{89}	mean diameter of D_8 and D_9	T	temperature of fluid
D_9	diameter of nozzle exit	u_2	impeller tip speed
D_h	hydraulic diameter	V_3	mean velocity in volute
D_w	diameter of wear-ring	V_{89}	mean velocity through area of $\pi D_{89}^2/4$
dH/dQ	slope of head-flow rate curve	V_9	mean velocity through nozzle exit
F_0	cross-sectional area of section 0-0	V_{m2}	meridian velocity at outlet
F_2	exit area of impeller	V_{u2}	tangential absolute velocity at outlet
F_8	throat area of volute	W	mean relative velocity of W_1 and W_2
F_9	cross-sectional area of nozzle exit	W_1	relative velocity at entrance of impeller
F_m	mean area of F_0 and F_8	W_2	relative velocity at exit of impeller
		$W_{2\infty}$	relative velocity at the exit of impeller with infinite number of blades

f_{geo}	impeller shape factor on disk friction loss	α	equivalent expansion angle of discharge nozzle
g	acceleration due to gravity	β_1	blade inlet angle
h	total hydraulic loss	β_2	blade discharge angle
h_l	total hydraulic loss	δ	thickness of sub-laminar layer
h_{id}	expansion loss in impeller	ΔV_{u2}	slip velocity at impeller outlet
h_{ie}	mixing loss behind impeller	η	pump efficiency
h_{if}	skin friction loss in impeller	η_h	pump hydraulic efficiency
h_V	total hydraulic loss in volute	η_V	pump volumetric efficiency
h_{Vde}	expansion loss in nozzle	η_m	pump mechanical efficiency
h_{Vdf}	skin friction loss in nozzle	θ	equivalent diffusion angle of impeller passage
h_{Vf}	skin friction loss in spiral body of volute	λ	skin friction coefficient
H	pump head	ν	kinematic viscosity of fluid
H_t	theoretical head of impeller	ξ	expansion loss coefficient
H_w	head of duty point for water	ξ_0	expansion loss coefficient when $Re \geq 4 \times 10^5$
K_Q	correction factor of flow rate to viscosity	ρ	density of fluid
k_s	roughness of wetted wall	σ	slip factor
L_i	blade length	Z	number of blades
L_K	length of discharge nozzle	ϕ_0	circumferential angle of tongue of volute
L_V	length of spiral body of volute	ψ_2	blockage factor of blade at outlet
n	pump rotating speed	ω	angular speed of impeller
n_s	specific speed of pump	Abbreviation	
P	shaft-power of pump	BEP	best efficiency point of pump
P_d	power due to disc friction of impeller	Subscription	
P_h	hydraulic power of pump	i	impeller
Q	pump flow rate	V	volute

1. INTRODUCTION

The effects of blade discharge angle of impeller on the performance of centrifugal pumps have been investigated since 1950s. Kamimoto and Matsuoka (1956) experimentally investigated various model centrifugal pump impellers with six logarithmic spiral blades with the constant angles of 30°, 50°, 70° and 90° respectively by using water as working fluid. The impeller was closed type and subject to a rotating speed of 1750r/min. It was made clear that the impeller with 30° discharge angle achieved best performance. The maximum variation of impeller hydraulic efficiency was as high as 40%. Varley (1961) conducted the experimental investigations into the effects of the blade discharge angle on the performance of a double suction centrifugal pump with specific speed of $36(n_s=3.65n\sqrt{Q}/H^{3/4}, \text{ r/min, m}^3/\text{s, m})$ when handling water. The pump rotating speed was 1400r/min. The impeller of the pump was closed and there were five blades in it. The blade pattern was a single arc. The inlet angle of the blade was 36°, the discharge angle were 15°, 27°, 40°, 59°, 74° and 88°, respectively. The results demonstrated that the head increased with increasing discharge angle, and the larger the flow rate, more was the increase in the head. When the blade discharge angle

was between 15° and 59°, the maximum variation of efficiency of the pump was only about 1.6%. Toyokuro et al (1979) made experiments on the influences of the discharge angle on the performance of a single-stage, end-suction and cantilevered centrifugal pump with specific speed 114 at rotating speed 1400r/min when handling water and viscous oils. The impeller was also closed type with six blades and the blade pattern was single arc too. The discharge angles were 23° and 65° respectively. The fluid viscosity was up to 390mm²/s (Reynolds number Re_2 was between 10^4 and 1.9×10^6) in the experiments. The results revealed that the head was improved as the discharge angle increased, the larger the flow rate was, and the more the head was improved. However, the efficiency of the pump for the discharge angle of 65° was just about 1% less than that of 23° when pumping water. Not only did the head increase with increasing discharge angle, but the efficiency was improved also by 8% while handling viscous oils. The higher the viscosity of oil was, the larger the improvement in efficiency. Tanaka and Ohashi (1984) made experiments on the series of semi-open, end-suction centrifugal pump impellers while transporting highly viscous oils with viscosity of 1-1500mm²/s (Reynolds number Re_2 was in the range of 4×10^2 - 1.0×10^6). The radial blades (90°) could achieve best performance for

high viscosity liquids. Aoki et al (1985) and Ohta et al (1990, 1996) experimentally studied the influences of the discharge angle on the performance of a single-stage, end-suction and cantilevered centrifugal pump with specific speed of 70 when handling water and viscous oils. The fluid viscosity was in the range of 1-650mm²/s (Reynolds number Re_2 was in 1.5×10^4 - 2.5×10^6). The impeller was closed or semi-open with six blades. The two-arc-shaped blade exit angles were 10°, 20°, 40°, 60°, 73°, respectively. The experimental results were similar to those of Toyokuro et al (1979).

In summary so far, when the centrifugal pumps handle water, one experiment shows the pump hydraulic efficiency can be improved by 40% with a variable blade exit angle (Kamimoto et al, 1956), but the other experiment indicates the pump efficiency just is improved by 1.6% (Varley, 1960). Obviously, this dispute needs to be confirmed experimentally. As the pump handling viscous oils, however, a consistent result seems to be achieved, i.e., the blade exit angle has substantial influence on both head and efficiency for model impellers. The results suggest large discharge angle is helpful to improve both head and efficiency for a liquid with higher viscosity than water.

The centrifugal oil pump with low specific speed has found significant applications in oilfields and refineries in China. What will happen in the performance for such a kind of pump when pumping various viscous oils for various blade discharge angles is interesting since this will result into an improved pump performance to save energy.

In this paper, a standard industrial centrifugal oil pump of type 65Y60 with low specific speed of 41.6 was employed as a test model and the effects of its blade discharge angle on the performance were investigated experimentally as the pump handled both water and viscous oils with various viscosities respectively. The results showed that the influence of the angle on the head was dominated at all viscosity conditions. The impeller with the discharge angle of 30° illustrated a best efficiency as the viscosity of liquid was less than 200mm²/s; however, as the viscosity was more than this value, the impeller with the discharge angle of 60° demonstrated highest efficiency. Moreover, a one-dimensional hydraulic model was proposed to investigate the effect of blade discharge angle analytically at various viscosities.

2. EXPERIMENTAL SETUP

2.1 Test rig

The sketch of the test rig for measuring the performance of centrifugal oil pump while handling water or viscous oil has been shown by Li (2002). The detail of the test rig can be found out in that reference. An oil temperature control system was installed in the tank of the rig in order to heat the oil and reduce its viscosity. The measurement

uncertainties of flow rate, head, shaft power and efficiency were 0.707%, 0.205%, 0.515% and 0.898%, respectively (Li, 2002).

2.2 Pump and Blades Patterns

The test pump was a standard industrial centrifugal oil pump of type 65Y60 with side-suction entry and single-stage, which has been extensively applied to transport clean crude oils and other liquid petroleum products at -40°C~+350°C in China (Fig. 1). The pump duty specifications are as follows: the flow rate $Q = 25 \text{ m}^3/\text{h}$, head $H = 60 \text{ m}$, rotating speed $n = 2950 \text{ r/min}$, specific speed $n_s = 41.6$. The impeller was closed type with five twisted three-dimensional blades (see Fig. 1c). The cross-sectional of the pump and impeller type have been shown in Fig. 1 (a) and (b). The main dimensions of the impeller are: $D_2 = 213 \text{ mm}$, $b_2 = 7.5 \text{ mm}$, $D_1 = 62 \text{ mm}$, $b_1 = 16 \text{ mm}$, $Z = 5$, $\beta_1 = 30^\circ$, $S_{u2} = 10 \text{ mm}$. The major dimensions of the volute are as follows: $D_3 = 240 \text{ mm}$, $b_3 = 16 \text{ mm}$, $D_9 = 60 \text{ mm}$, $F_8 = 858 \text{ mm}^2$, $L_k = 250 \text{ mm}$, $\varphi_0 = 36^\circ$.




Fig. 1. Pump cross-sectional view (a), impeller style (b) and blade pattern (c)

2.3 Working liquids

The three impellers with discharge angle, β_2 , 15°, 45° and 60°, were prepared to illustrate their influence on the performance of the pump. Except the blade length, or the blade warp angle and S_{w2} were different from that of the original impeller with a discharge angle of 30°, the other geometrical dimensions remained unchanged. The number of blades of those impellers was five and the blade patterns were NURBS curves. The comparison of the four blade patterns has been demonstrated in Fig.1 (c).

The working liquids were both water and China 100# machine oil in the performance experiments respectively. It was made sure that both liquids are Newtonian fluid by using a rotating dynamic viscosity meter. The density and kinematical viscosity of water are 1000kg/m³, 1mm²/s at 20°C respectively. However, the density and dynamic as well as kinematical viscosities of the oil demonstrated fairly variation with temperature in the experiments when the temperature was varied in the range of 15°C-65°C. Subsequently, based on the test data, the formula for calculating the density and kinematical viscosity of the oil was written as

$$\begin{cases} \rho = 906.653 - 0.5267T \\ v = \frac{1000}{1.0112 \times 10^{-2} T^2 - 0.2222T + 2.8658} \end{cases} \quad (1)$$

The values of the kinematical viscosity of working liquids, such as 1(water), 29, 45, 75, 98, 134, 188 and 255mm²/s (oil), were chosen in the experiments. The performance tests were conducted in such a way that the oil temperature was raised from low to high in order to control its viscosity conveniently. The oil temperature was monitored both in the oil tank and in the pump inlet nozzle. Usually, the oil temperature rises less than 2°C during a performance test. In those experiments, Reynolds number Re_2 was in the range of $1.37 \times 10^4 - 3.5 \times 10^6$ in the experiments.

3. EXPERIMENTAL RESULTS

3.1 Performance Curves

Figure 2 shows the variation of head curve versus flow rate when the viscosities of working liquid are 1, 98 and 255mm²/s, respectively. A larger discharge angle causes the pump to develop a higher head than the smaller one does. As the viscosity is 1mm²/s, the peak head has occurred at a flow rate of $Q=8\text{m}^3/\text{h}$; rather than at zero flow rate. This is so-called unstable or hooked shape head curve effect. Unfortunately, such an unstable curve disappears gradually with increasing viscosity. No matter whatever value the viscosity is, the maximal change of the head curve due to the discharge angle variation almost maintains the same amount, i.e., the effect of discharge angle on the head curve seems to be independent upon the viscosity of the working liquid. Hence, changing

discharge angle should be an effective way for altering the head of centrifugal oil pumps.




Fig. 2 Head curves in terms of flow rate at three viscosity values

Figure 3 illustrates the variation of shaft power curves in terms of flow rate as the viscosities of working liquid are 1, 98 and 255mm²/s as well. Like the head curves, the effect of the discharge angle on the shaft-power curve appears to be independent on the viscosity of the working liquid. Further, the larger discharge angle definitely consumes more power than the smaller one does.

Figure 4 demonstrates the variation of the efficiency curves against flow rate while the viscosities of




Fig. 3 Shaft-power curves in terms of flow rate at three viscosity values

working liquid are 1, 98 and 255mm²/s. First of all, the efficiency reduces continuously with increase in viscosity. Unlike those in the head curves, the effect of the discharge angle on the efficiency curve is dependent on the viscosity of the working liquid. As the viscosity is less than 200mm²/s, the efficiency of the pump with a discharge angle of 30° is higher than that with an angle of 60°. However, for the viscosity more than 200mm²/s, the situation is reversed.

3.2 Hydraulic Parameters at BEP

In order to illustrate the effect of viscosity on the performance of the centrifugal oil pump with various discharge angles more clearly, Fig. 5 is applied to




Fig. 4 Efficiency curves against flow rate at three viscosity values

show the hydraulic parameters, such as head, hydraulic power and efficiency at the best efficiency point (BEP) against viscosity. The impeller with a discharge angle of 60° always develops higher head than the others at the BEP. As the viscosity is greater than 200mm²/s, the head is improved by 10%; as the viscosity is up to 255mm²/s, the efficiency is increased by 3% compared to the original impeller with 30° exit angle. However, at the high flow rates, the efficiency is improved by 6%. The reason for this is that the hydraulic power of the impeller with 60° discharge angle drops down very slowly than the others with increasing viscosity. A similar behavior was observed




Fig. 5 Head (a), hydraulic power (b) and efficiency (c) at BEP in terms of viscosity

in the precious studies (Toyokuro et al, 1979; Tanaka and Ohashi, 1984; Ohta and Aoki, 1990). This fact seems to reveal that the blade exit angle effect on the pump head and efficiency is nearly equal. When a pump pumping water, it was shown experimentally that the blade exit angle effect was dominated on the pump efficiency (Kamimoto and Matsuoka, 1956) rather than on the head. However, the result was discovered that the effect on the head not efficiency was substantial (Varley, 1961). Our current results don't agree with them.

From the point of view of efficiency, while the viscosity of liquid is less than 200mm²/s, the performance of the original impeller with a discharge angle of 30°, is best. However, while the viscosity is greater than this value, the performance of the newly designed impeller with a discharge angle of 60° is best. The impeller with an exit angle less than 30° has a very poor performance.

3.3 Slip Factor

The slip factor is used to specify the flow effect in the exit of a centrifugal pump impeller and is a key parameter to establish a theoretical head developed by the impeller. There are several versions of definition for the slip factor (Qiu, Mallikarachi and Anderson, 2007). However, the following definition (Brennen, 1994) is accepted in this paper

$$\sigma = \frac{u_2 - \Delta V_{u2}}{u_2} = 1 - \frac{\Delta V_{u2}}{u_2} \quad (2)$$

where the slip velocity of fluid (Fig. 6) depends on the impeller geometry and flow rate as well as fluid viscosity etc. Traditionally, the slip factor of a centrifugal pump impeller is frequently estimated by means of the Weisner's or Stodola's formulas. The Weisner's expression is read as (Brennen, 1994)

$$\sigma = 1 - \frac{\sqrt{\sin \beta_2}}{Z^{0.7}} \quad (3)$$

and the Stodola's relation is written as (Brennen, 1994)

$$\sigma = 1 - \frac{\pi \sin \beta_2}{Z} \quad (4)$$

These equations do not involve the effects of both fluid viscosity and flow rate on the slip factor.




Fig. 6 Velocity triangle at impeller exit

It is interesting to note that a slip factor of centrifugal pump impeller can also be calculated based on the pump experimental performance curve and impeller geometry (Li, 2004). The following equation is used to estimate the slip factor at BEP

$$\sigma = \frac{g}{2u_2^2} \left[2H - Q \left(\frac{dH}{dQ} - \frac{u_2}{g\eta_v F_2 \tan \beta_2} \right) \right] \quad (5)$$

where the volumetric efficiency, η_v was calculated by using Stepanoff's method by using the geometrical parameter of both wear-rings installed in the impeller

shroud and hub and the ring radial clearance as well as the pressure differential across the up and down streams of the ring (Stepanoff, 1948). The details of the calculation are available in Li (2004).

Figure 7 illustrates the slip factor at BEP as a function of blade discharge angle at the viscosities of 1, 98 and 255 mm²/s. From Fig. 7, it was learnt that no matter whatever value the viscosity is, the slip factors calculated by using the experimental head-flow rate relations decrease with increasing blade discharge angle




Fig. 7 Slip factor as a function of blade exit angle at three viscosity values at BEP

angle. The fluid viscosity does affect the slip factor, but the effect is not substantial. These findings are consistent with those illustrated by Toyokuro et al (1979) and Ohta (1999).

If regardless of the viscosity effect, the scattered points of the slip factors estimated via the experimental data can be represented by the following linear equation with respect to the blade discharge angle

$$\sigma = 0.690689 - 0.00106984\beta_2 \quad (6)$$

Moreover, the slip factors established by the Weisner's and Stodola's formulae show extremely large difference from those determined by the experimental data. This suggests that if those expressions are applied to estimate the slip factors for highly viscous oils, significant errors will be caused.

4. Model Exit Angle Effect

The centrifugal pump performance prediction was traditionally based on the hydraulic losses analysis in a pump (Aisenstein, 1927; Pigott, 1945; Rathod & Donovan, 1980; Takagi et al, 1980; Stirling, 1982; Aly & Al-Zubaidy, 1992; Yoon et al, 1998; Oh & Chung, 1999; Zaher, 2001). In those predictions, the fluid viscosity remains unchanged. More recently, the effect of fluid viscosity on centrifugal pump efficiency was shown analytically with the scaling laws related to the pump mechanical, volumetric and hydraulic efficiencies (Gulich, 1999a; 1999b; 2003).

The performance of three centrifugal pumps was evaluated by considering blade loading loss and impeller and volute friction loss based on pip flow at varieties of fluid viscosity (Hamkins and Hergt, 1987). Unfortunately, any useful equations for estimating those losses were not presented by them at all. The hydraulic losses in centrifugal oil pumps were calculated by using the boundary layer theory in fluid mechanics at different viscosities of liquid pumped to explore the cause for the "sudden-rising head" in the pumps (Li, 2000). However, in the calculation the diffusion loss in the impellers was ignored.

In this section, it is intended to theoretically investigate the effect of exit blade angle on the pump performance at different viscosities of fluid at the pump duty point and to compare with the experimental observations. In fact, such an investigation is eventually equivalent to how to exactly estimate hydraulic losses inside the pump, causing precise predictions of the performance parameters at those viscosities.

4.1 Hydraulic Loss Model

It is assumed the flow in the pump is one-dimensional, steady, laminar or turbulent. Since the fluid velocity in the side-entry of the pump shown in Fig. 1 (a) is much lower than those in the impeller and volute, the hydraulic losses can be ignored in the entry. Just the losses across the impeller and volute are considered here. It is believed that the angle of attack to the entrance of blade is so small that the shock loss at the entrance also can be neglected. Therefore, a flow just suffers from skin friction and diffusion losses in an impeller. For the volute, a flow is subject to the skin friction loss in the spiral body as well as skin friction loss and diffusion in the discharge nozzle. A mixing loss occurs at the boundary between the impeller exit and volute inlet.

For convenience, the complicated flow passages in the impeller and volute are converted into straight circular pipes by using hydraulic diameter properly; the skin friction coefficients for such pipes are applied to determine the friction loss in the actual flow passages.

The experimental centrifugal oil pump is a low specific speed pump because the specific speed of its impellers is just around 41. In the impellers of such a pump, the expansion of the cross-sectional area of flow channels is much large in the radial direction, even a slight contraction in the axial direction. Consequently, the impellers are subject to a diffusion loss, which must be taken into account in a hydraulic loss model.

4.2 Hydraulic Loss in Impeller

The major dimensions of the impeller and volute were sketched in Fig. 7. The hydraulic losses in the impeller consist of the skin friction and diffusion losses. The following expression is employed to figure out the friction loss

$$h_{if} = \lambda \frac{L_i W^2}{D_{hi} 2g} \quad (7)$$

where the blade length L_i on the mean stream-surface was correlated to the blade exit angle β_2 of four experimental impellers in the following equation

$$L_i = 0.0033\beta_2^2 - 0.4567\beta_2 + 27.5 \quad (8)$$




Fig. 7 Major dimensions of impeller (a) and volute (b)

The mean relative velocity of fluid through the impeller passages W is equal to half sum of those in the blade inlet and outlet, respectively

$$W = (W_1 + W_2)/2 \quad (9)$$

The hydraulic diameter D_{hi} is estimated by the formula

$$D_{hi} = \frac{1}{2} \left(\frac{4\pi D_1 b_1}{Z} + \frac{4\pi D_2 b_2}{Z} \right) \quad (10)$$

Further, the equation can be simplified as follows

$$D_{hi} = \frac{D_1 b}{Z b_1 + \pi D_1} + \frac{D_2 b_2}{Z b_2 + \pi D_2} \quad (11)$$

The skin friction coefficient, λ , depends on the flow regime in the passages and Reynolds number Re_i ($Re_i = W D_{hi} / \nu$) and the roughness of wetted surfaces, k_s .

The diffusion loss in the impellers can be calculated by using the following equation

$$h_{id} = \xi \frac{W_1^2}{2g} \quad (12)$$

The diffusion coefficient ξ is dependent on the equivalent expansion angle of the impeller flow passage θ , which is determined by

$$\theta = 2 \tan^{-1} \left[\frac{\pi(D_2 - D_1)}{2ZL_i} \right] \quad (13)$$

For the pervious experimental impellers, the equivalent expansion can be expressed in terms of blade discharge angle

$$\theta = -0.0001\beta_2^2 + 0.0099\beta_2 + 0.1262\beta_2 + 19.6618 \quad (14)$$

4.3 Hydraulic Loss in Volute

There are three kinds of hydraulic loss in the volute. One is the skin friction loss in the spiral body, one is the friction and diffusion losses in the discharge nozzle and one is the mixing loss behind the impeller.

The friction loss along the wall of the spiral body can be calculated by using the following equation

$$h_{if} = \lambda \frac{L_v V_3^2}{D_{hv} 2g} \quad (15)$$

The hydraulic diameter D_{hv} is related to the mean cross-section area of the volute as follows

$$D_{hv} = \frac{4F_m}{b_3 + 2F_m/b_3} \quad (16)$$

The mean cross-section area is decided by the areas of the cross-sections 0-0, F_0 , and 8-8, F_8 as follows

$$F_m = \frac{1}{2}(F_0 + F_8) \quad (17)$$

Note that the area $F_0 = 0.5(D_3 - D_2)b_3$ and F_8 has included the area of $0.5(D_3 - D_2)b_3$.

The mean velocity of fluid, V_3 , in the volute is simply estimated via

$$V_3 = Q(1 - \phi_0/360)/F_8 \quad (18)$$

The length of the spiral body, L_v , is determined by using the expression

$$L_v = \pi D_3(1 - \phi_0/360) \quad (19)$$

Likewise, the skin friction coefficient, λ , also depends on the flow regime in the volute and Reynolds number Re_v ($Re_v = V_3 D_{nv}/\nu$) and the roughness of wet surfaces, k_s .

The skin friction loss in the discharge nozzle is estimated by means of the following expression

$$h_{vdf} = \lambda \frac{L_s}{D_{s9}} \frac{V_{s9}^2}{2g} \quad (20)$$

The mean diameter of the discharge nozzle can be determined by

$$D_{s9} = \frac{1}{2}(D_8 + D_9) \quad (21)$$

The equivalent diameter of the section 8-8 is given by

$$D_8 = \sqrt{\frac{4F_8}{\pi}} \quad (22)$$

The velocity of fluid through the pipe with a diameter of D_{s9} is calculated by the equation

$$V_{s9} = Q/F_{s9} \quad (23)$$

where the mean area $F_{s9} = \pi D_{s9}^2/4$. The skin friction coefficient, λ , is in terms of the Reynolds number Re_d ($Re_d = V_{s9} D_{s9}/\nu$) and the roughness of wet surfaces, k_s .

The diffusion loss in the discharge nozzle is determined by the following equation

$$h_{vde} = \xi \frac{V_3^2}{2g} \quad (24)$$

The diffusion loss coefficient ξ is dependent on the equivalent expansion angle of the discharge nozzle, α , is written as

$$\tan \frac{\alpha}{2} = \frac{D_9 - D_8}{2L_k} \quad (25)$$

The mixing loss behind an impeller is considered to be the loss due to a sudden expansion of the meridian flow and the loss due to turbulent or laminar shearing effect in the tangential direction between flow exiting the impeller and that in the volute. The mixing loss behind the impeller is calculated by the equation

$$h_{ie} = \frac{[1 - b_2/b_3]V_{m2}^2 + (V_{u2} - V_3)^2}{2g} \quad (26)$$

The first term in Eq. (26) is according to the sudden expansion loss in White (1994), but the second term is proposed by the author of this paper.

4.4 Hydraulic Parameter Estimate

For the volumetric efficiency of the pump, η_v , is slightly increased by a higher viscosity of liquid pumped (Kurokawa, 1990). Since its variation is very small, it is simply estimated by using the Lomakin's empirical equation (Kurokawa, 1990)

$$\eta_v = \frac{1}{1 + 0.68n_s^{2/3}} - 0.07 \quad (27)$$

Note that the second term is added into Eq. (27) by the author of this paper to approximately account for the effect of the wear-ring and balancing holes in the experimental impeller hubs on the volumetric efficiency.

The hydraulic efficiency of the pump, η_h can be determined according to the theoretical head and total hydraulic losses in the impeller and volute. It is expressed by

$$\eta_h = 1 - \frac{h_l}{H_t} \quad (28)$$

The total hydraulic loss, h_l , is the sum of all the losses in the impeller and volute, it is read as

$$h_l = h_{if} + h_{id} + h_{ie} + h_{vif} + h_{vdf} + h_{vde} \quad (29)$$

The theoretical head generate by the impeller, H_t , depends on the flow rate and impeller geometry as well rotating speed. It is specified by the Euler equation for turbomachine

$$H_t = \frac{u_2}{g} \left(\sigma u_2 - \frac{Q}{\eta_v \pi D_2 b_2 \psi_2 \tan \beta_2} \right) \quad (30)$$

The slip factor has been decided with Eq. (6). The blade blockage coefficient at the outlet, ψ_2 , is calculated via the expression

$$\psi_2 = 1 - ZS_{u2}/\pi D_2 \quad (31)$$

The mechanical efficiency of the pump is estimated by using the mechanical loss and shaft-power as follows

$$\eta_m = 1 - \frac{1.5P_d}{P} \quad (32)$$

It was found that the measured disc friction losses in the actual impellers usually were higher than those estimated with empirical equations (Nemdili and Hellmann, 2007). The factor 1.5 in Eq. (32) is used to take this effect into account. The disk friction power loss of the impeller, P_d , is calculated by the following equation (Gulich, 1999a)

$$P_d = \frac{1}{2} C_M f_{geo} \rho \omega^3 (R_2^5 - R_w^5) \quad (33)$$

where f_{geo} is the a shape factor for closed shape impellers of centrifugal pump, $f_{geo}=1.21$ (Gulich,1999a). The torque coefficient due to disk friction on the impeller shroud and hub, C_M is written as (Schlichting, 1968)

$$C_M = \begin{cases} 2\pi(R_2/t)(1/Re_2) & Re_2 \leq 4 \times 10^4 \\ 2.67/Re_2^{0.5} & Re_2 \leq 3 \times 10^5 \\ 0.0622/Re_2^{0.2} & Re_2 > 3 \times 10^5 \end{cases} \quad (34)$$

The disk Reynolds number based on the impeller diameter is defined by $Re_2 = D_2^2 \omega / 4\nu$. The shaft-power that the pump consumed is expressed by

$$P = \rho g Q H_i + 1.5 P_d \quad (35)$$

The theoretical flow rate through the impeller is $Q_t = Q/\eta_v$. The gross efficiency of the pump can be estimated by means of the available volumetric, hydraulic and mechanical efficiencies via

$$\eta = \eta_h \eta_v \eta_m \quad (36)$$

At the same time, the actual head generated by the pump and the flow rare through the pump can be predicted by using the following equations accordingly. The head is read as

$$H = H_i - h_i \quad (37)$$

And the flow rate

$$Q = K_q Q_w \quad (38)$$

The flow rate of pumped water at design duty Q_w is specified. However, it will get small with increasing viscosity of fluid because of viscous effect. The correction factor for such an effect is correlated to the viscosity with $K_q = 1.1051 \times 10^{-8} \nu^3 - 5.6347 \nu^2 + 8.3088 \times 10^{-5} \nu + 0.9888$.

4.5 Friction and Diffusion Loss Coefficients

When the Reynolds number $Re \leq 2300$, the flow in a straight duct with circular cross-section is laminar regime, and the skin friction coefficient is determined by the following formula (Schlichting, 1968)

$$\lambda = \frac{64}{Re} \quad (39)$$

For the impeller, $Re = Re_i$; for the volute, $Re = Re_v$; but for the discharge nozzle, $Re = Re_d$.

When $Re > 2300$, the flow in the impeller or volute is turbulent. If $k_s/\delta \leq 1$, then the flow is in the turbulent smooth regime. In this case, the friction coefficient λ is independent of the relative roughness

k_s/D_h (k_s/D_{h_i} or k_s/D_{h_v} or k_s/D_{h_d}), but correlated to the Reynolds number Re (Re_i or Re_v or Re_d). The corresponding friction loss coefficient is written as (Schlichting, 1968)

$$\frac{1}{\sqrt{\lambda}} = 2.0 \lg(Re \sqrt{\lambda}) - 0.8 \quad (40)$$

The roughness of wet surfaces is $k_s = 6Ra$ for the casted walls. For the cast impeller and volute in the paper, the roughness height, which is rated as the arithmetic average deviation of the surface valleys and peaks, is $Ra = 40 \mu m$. The thickness of the sub-laminar layer is expressed by $\delta = 14.1(D_h/Re \sqrt{\lambda})$.

If $1 < k_s/\delta \leq 14$, then the flow is in the turbulence transition zone. Consequently, the friction loss coefficient λ depends on both Re and k_s/D_h , and is read as (Schlichting, 1968)

$$\frac{1}{\sqrt{\lambda}} = 1.74 - 2 \lg \left(\frac{2k_s}{D_h} + \frac{18.7}{Re \sqrt{\lambda}} \right) \quad (41)$$

However, if $k_s/\delta > 14$, then the flow is in the complete turbulence rough zone, causing the coefficient λ just related to k_s/D_h and shown as follows (Schlichting, 1968)

$$\lambda = \frac{1}{\left(1.74 - 2 \lg \frac{2k_s}{D_h} \right)^2} \quad (42)$$

The impeller and volute discharge nozzle are subject to a diffusion loss. A coefficient related to such a diffusion loss is considered to be equal to that in conical diffusers approximately. Through fitting the curves of diffusion loss coefficient in a conical diffusers with fully developed inlet flow, an empirical relation is got to estimate such a coefficient for any diffusion angle (White, 1994)

$$\xi = \begin{cases} \xi_0 & Re \geq 4 \times 10^5 \\ \xi_0 + 0.0131 \ln(4 \times 10^5 / Re) & Re < 4 \times 10^5 \end{cases} \quad (43)$$

where $\xi_0 = -2 \times 10^{-7} \theta^4 + 4 \times 10^{-5} \theta^3 - 2.9 \times 10^{-3} \theta^2 + 0.1096 \theta - 0.586$. The last term in the second expression in Eq. (43) is proposed by the author of this paper to involve low Reynolds number effect on the diffusion loss coefficient based on the experimental data presented in Fried and Idelchik (1989). For the volute discharge nozzle, angle θ should be replaced with the nozzle equivalent expansion angle α .

4.6 Computed Results

The computations were conducted at the duty point $Q_w = 25\text{m}^3/\text{h}$ for the density $\rho = 1000$ (water), 892.96, 890.85, 888.22, 885.58, 882.95, 877.16, 870.84(oil) kg/m^3 and $\nu = 1$ (water), 29, 45, 75, 98, 134, 188 and




Fig. 8 Computed head (a), shaft-power (b) and efficiency (c) at duty point in terms of blade exit angle

$255\text{mm}^2/\text{s}$ (oil), respectively. The blade discharge angle was varied between 15° and 60° .

The results for just the viscosities of 1, 45, 188 and $255\text{mm}^2/\text{s}$ are shown to get more tidy plots. The head and shaft-power and total efficiency in terms of blade exit angle are illustrated in Fig. 8 for different viscosities at duty point. They can be compared with

the experimental data in Fig. 9. The head estimated rises with increasing blade exit angle but reduces steadily with increasing viscosity. Note that more change of head happens when the exit angle is




Fig. 9 Experimental head (a), shaft-power (b) and efficiency (c) at duty point in terms of blade exit angle

between 15° and 35° . Such variation trend seems to agree with that of experiments.

The computed shaft-power gets large with increasing viscosity and blade discharge angle simultaneously. However, it really has a smaller rising slope than the experimental curves. The reason for this perhaps is Eq. (34) of the torque coefficient C_M for rotating disks is




Fig. 10 Estimated hydraulic (a) and mechanical (b) efficiencies at duty point in terms of blade exit angle

unable to account for the disk friction over the actual impellers with complicated shroud and hub geometry exactly. This problem highly is expected to be confirmed with experiment or CFD simulation.

Like the experimental pump efficiency, the estimated one is highly viscosity-dependent. Moreover, the optimal blade exit angle for best efficiency occurs at around 30° at less viscosity, but with increasing of viscosity the optimal exit angle prefers to be large one. This feature has been demonstrated in Fig. 8 clearly by using the peak efficiency curve. Note that for the experimental pump efficiency in Fig. 9, maximum efficiency is obtained at $\beta_2 = 30^\circ$ for $\nu \leq 180 \text{ mm}^2/\text{s}$ and for $\nu = 255 \text{ mm}^2/\text{s}$ the peak efficiency is achieved at $\beta_2 = 60^\circ$.

The hydraulic efficiency is shown in Fig. 10 for various viscosities in terms of blade discharge angle at duty pump. The effect of viscosity on the hydraulic efficiency much resembles to that on the pump total efficiency. The hydraulic efficiency is reduced substantially by the increasing viscosity. However, at low viscosity, a relative small blade angle allows the pump to have best hydraulic efficiency; contrarily a relative large blade angle ensures the pump to achieve best performance at high viscosity. Such a variation




Fig. 11 Hydraulic losses in impeller (a) and volute (b) at duty point in terms of blade discharge angle

of the hydraulic efficiency with the blade exit angle appears to be responsible for the effect of the angle on the pump efficiency as shown in Fig. 9.

The mechanical efficiency is given in Fig. 10 as a function of blade discharge angle as well. It is noted that the mechanical efficiency is significantly affected by viscosity, but it is just slightly increased with increasing discharge angle.

It is the dramatic reduction in the hydraulic and mechanical efficiencies that should contribute to the degraded performance of a centrifugal oil pump with increasing viscosity.

The skin friction loss in the impellers has been demonstrated in Fig. 11 (a) in terms of blade exit angle for different viscosities. This loss is very dominated in the impellers with a small discharge angle rather than a large angle at high viscosity. It suggests that for pumping highly viscous liquids an impeller having large blade angle should be more efficient compared to one with small blade angle.

The friction loss in the volute is available in Fig. 11 (b). With increasing blade exit angle, a steady but slow increase loss is found out. This indicates an impeller





Fig. 12 Friction loss factor in terms of Reynolds number in impeller (a) with $\beta_2=30^\circ$ and volute (b), figures in plot show viscosities of fluid

with large blade angle has a negative effect on the performance of volute.

The friction loss in the impellers shows a little variation when $\nu \leq 98 \text{mm}^2/\text{s}$. The small friction loss coefficients, shown in Fig. 12 (a), are responsible for this effect. The friction loss in the volute also is slightly increased when $\nu \leq 45 \text{mm}^2/\text{s}$. Likewise, in that case, small friction loss factors are found out in Fig/ 12 (b).

The diffusion losses in the impeller and behind the impeller have been plotted in Fig. 13 (a) and (b), respectively, at various viscosities. The diffusion loss is slightly viscosity-dependent and gets significantly large with increasing blade exit angle. Compared to the friction loss in the impeller in Fig. 11(a), the diffusion loss is quit substantial, so that the expansion of cross-sectional area of impeller passages should be carefully controlled to make the diffusion loss as small as possible. The expansion loss behind the impeller grows quickly when $\beta_2 < 40^\circ$, but slowly when $\beta_2 \geq 40^\circ$. This loss magnitude is comparable to the skin friction loss in the impeller but much smaller than that in the volute.





Fig. 13 Estimated diffusion (a) and sudden expansion as well as mixing losses (b) at BEP in terms of blade exit angle

The expansion loss behind the impeller consists of a sudden expansion loss in meridian plane and a mixing loss in the tangential direction. It was shown experimentally that the sudden expansion loss was independent when Reynolds number is in a range of $(3-6) \times 10^4$ for turbulent flows (Iguchi and Ohmi, 1986). Moreover, for laminar flow, the loss wasn't changed significantly until Reynolds number less than 100 (Oliveira and Pinho, 1997; Oliveira, Pinho and Schulte, 1998). In our case, since the Reynolds number is more than 900, the sudden expansion loss can be considered to be viscosity-independent. The mixing loss may be affected by Reynolds number, but no relevant evident is found in literature, so that it has to be treated regardless of viscosity of fluid.

The total head loss and ratio of total hydraulic loss in the impeller to that in the volute have been shown in Fig. 14 (a) and (b). The total head loss grows steadily with increasing blade exit angle and viscosity of fluid, especially when the viscosity is more than $45 \text{mm}^2/\text{s}$. The ratio of head loss is in the range of 0.6-0.9 and depends on both blade exit angle and viscosity of fluid. This suggests that for a small blade exit angle the hydraulic losses in the impeller are comparable to those in the volute; however, as the blade angle




Fig. 14 Ratio of hydraulic losses in impeller to those in volute at BEP in terms of blade discharge angle

increasing, the losses in the impeller are around 60% of the losses in the volute, especially when viscosity is higher than $98\text{mm}^2/\text{s}$. This implies the volute may play important role in the pump performance, so that it should be designed as perfectly as possible, especially for highly viscous liquids. Note that these findings are consistent with the results presented in Li (2000) by using the boundary layer theory.

At the viscosity of $45\text{mm}^2/\text{s}$, the ratio of hydraulic loss is higher than that at $1\text{mm}^2/\text{s}$. The reason underlying this effect is that the diffusion loss in the impeller is increased remarked at $45\text{mm}^2/\text{s}$ shown in Fig. 13(a).

The experiments on the model pumps with two impellers of 23° and 65° discharge blade angles and 107 specific speed (Toyokura, Kurokawa and Kanemoto, 1979), the pump with the impeller of 65° exit angle showed a better efficiency than that of 23° angle at a viscosity of $45\text{mm}^2/\text{s}$ ($Re_e = 3.58 \times 10^5$) yet. However, in our case, the pump with the impeller of 60° discharge angle demonstrated a higher efficiency compared to that of 30° angle at a viscosity as high as $255\text{mm}^2/\text{s}$ ($Re_e = 1.37 \times 10^4$). The effect of blade discharge angle on the pump performance in our case doesn't seem to be stronger at various viscosities. The




Fig. 15 Comparison of head (a) and efficiency (b) between original and redesigned cases, solid line is for redesigned case and dashed line is for original case

reason for this may be the specific speed of the industrial pump used in the experiments is just 41.6, less than half of the specific speed of the model pumps. The specific speed effect should need to be investigated in future.

Since the friction loss in the volute is primary as shown in Fig. 11 (b), the volute cross-section area is enlarged by 44% (width and height are increased by 20%, respectively) to reduce such a loss. In order to keep the ratio b_2/b_3 unchanged, the width of blade exit b_2 also is increased by 20%. Fig. 15 illustrates the comparison of head and efficiency between the original and redesigned cases. It is clear that the pump with increased volute cross-section and enlarged blade exit width does get a better performance, especially at small blade exit angle ($\beta_2 \leq 35^\circ$). The hydraulic diameters of the volute and impellers are increased to 28.4mm and 19.8mm from 24.6mm and 18.4mm, respectively. As a result, the peak pump efficiency is improved by 1% and the head is increased by 3.7% when $\beta_2 = 30^\circ$.

5. CONCLUSION

The effects of blade discharge angle on the performance of a centrifugal oil pump have been investigated experimentally and analytically while the pump handles water and other viscous oils. The hydraulic loss in the impeller and volute has been calculated in terms of both viscosity and blade exit angle by using a model on the fluid mechanics base. The following conclusions can be drawn: (1) the blade discharge angle has a strong but equal influence on the head, shaft power and efficiency of the centrifugal oil pump for various viscosities of liquids pumped; (2) The rapid reduction in the hydraulic and mechanical efficiencies is responsible for the pump performance degradation with increasing viscosity of liquids; (3) at all viscosity values, the volute shows significant effect on the performance, it should be designed as perfectly as we can; (4) the theoretical hydraulic loss model is able to get broadly similar behaviour to the experimental curves; (5) For the hydraulic loss model is subject to limitations, it has been planned that the effect of blade exit angle will be investigated numerically by using CFD code, such as Fluent. It is hopeful the results will be available soon.

ACKNOWLEDGEMENTS

The research was conducted under a grant awarded through the Key Research and Development Program for the Quality Research Groups at Lanzhou University of Technology. The university was fairly acknowledged; additionally the previous postgraduate student Dr FY Lei and technicians Mr FZ Su and C Xiao are also appreciated very much for their fantastic contributions in laboratory.

REFERENCES

- Aisenstein, M. D. (1927). A new method of separating the hydraulic losses in a centrifugal pump. *ASME Transactions* 49, 1-7.
- Aly, S. and S. Al-Zubaidy (1992). Performance prediction method for centrifugal pumps. SAE paper 921731.
- Aoki, K., H. Ohta, and Y. Nakayama (1987). Study on centrifugal pump for high viscosity liquids (the 1st report, effect of impeller output angle and number of blades on the pump performance of closed type impellers). *Proceedings of the School of Engineering, Tokai University* 27(2), 151-158.
- Aoki, K., T. Yamamoto, H. Ohta, and Y. Nakayama (1985). Study on centrifugal pump for high viscosity liquids. *Trans JSME, Series B* 51(468), 2753-2758.
- Brennen, C. E. (1994). *Hydrodynamics of Pumps*. Oxford, UK: Oxford University Press, 48-51.
- Fried, E. and I. E. Idelchik (1989). *Flow Resistance: a Design Guide for Engineer*. New York, USA: Hemisphere Publishing Corporation, 111-114.
- Gulich, J. F. (1999a). Pumping highly viscous fluids with centrifugal pumps-part 1. *World Pumps* 395, 30-34.
- Gulich, J. F. (1999a). Pumping highly viscous fluids with centrifugal pumps-part 2. *World Pumps*, 396, 39-42.
- Gulich, J. F. (2003). Effect of Reynolds number and surface roughness on the efficiency of centrifugal pumps. *ASME Journal of Fluids Engineering* 125, 670-679.
- Hamkins, C. P. and P. H. Hergt (1987, May). Prediction of viscosity effects in centrifugal pumps by consideration of individual losses. In *Proceedings of the Third European Congress on Fluid Machinery for the Oil, Petrochemical and Related Industries*, Hague, Netherlands, pp. 207-217.
- Iguchi, M. and M. Ohmi (1986). Loss coefficients for flows through a sudden expansion and a sudden contraction closely placed. *Trans JSME, Series B* 52(481), 3252-2258.
- Kamimoto, G. and Y. Matsuoka (1956). On the flow in the impeller of centrifugal type hydraulic machinery (the 2nd report). *Trans JSME, Series 3* 22(113), 55-59.
- Kurokawa, J. (1990, April). Simple formulae for volumetric efficiency and mechanical efficiency of hydraulic machinery. In *Proceedings of the 3rd Japan-China Joint Conference on Fluid Machinery*, Osaka, Japan, pp. 101-108.
- Li, W. G. (2000). The "sudden-rising head" effect in centrifugal oil pumps. *World Pumps* 409, 34-36.
- Li, W. G. (2002). The Influence of number of blades on the performance of centrifugal oil pumps. *World Pumps* 427, 32-35.
- Li, W. G. (2004). A method analyzing the performance of centrifugal oil pumps. *ASME Journal of Fluids Engineering* 126(3), 482-485.
- Ohta, H (1999). Effect of Reynolds number of slip factor of centrifugal pump for high viscosity liquids. *Trans JSME, Series B* 65(639), 3697-3704.
- Nemdili, A. and D. H. Hellmann (2007). Investigations on fluid friction of rotational disks with and without modified outlet sections in real centrifugal pump casing. *Forsch Ingenieurwes* 71, 59-67.
- Oh, H. W. and M. K. Chung (1999). Optimum values of design variables versus specific speed for centrifugal pumps. *Proc Instn Mech Engrs, Part A* 213, 219-226.
- Ohta, H., and K. Aoki (1990). Study on centrifugal pump for high-viscosity liquids (effect of impeller

- output angle on the pump performance). *Proceedings of the School of Engineering, Tokai University* 30(1), 175-183.
- Ohta, H. and K. Aoki (1996). Effect of impeller angle on performance and internal flow of centrifugal pump for high-viscosity liquids. *Proceedings of the School of Engineering, Tokai University* 36(1), 159-168.
- Oliveira, P. J. and F. T. Pinho (1997). Pressure drop coefficient of laminar Newtonian flow in axisymmetric sudden expansions. *International Journal of Heat and Fluid Flow* 18(5), 518-529.
- Oliveira, P. J., F. T. Pinho, and A. Schulte (1998). A general correlation for the local loss coefficient in Newtonian axisymmetric sudden expansions. *International Journal of Heat and Fluid Flow* 19, 655-660.
- Pigott, R. J. (1945). Prediction of centrifugal-pump performance, *ASME Transactions*, 67, 439-449.
- Qiu, X. W., C. Mallikaratchi, and M. Anderson (2007, May). A new slip factor model for axial and radial impellers. In *Proceedings of GT2007-Power for Land, Sea and Air*, Montreal, Canada.
- Rathod, M. S. and F. M. Donovan (1980, March). Performance evaluation of a centrifugal cardiac pump. In *Proceedings of the Conference on Performance Prediction of Centrifugal Pump and Compressors*, New Orleans, USA, pp. 235-243.
- Schlichting, H. (1968). *Boundary-Layer Theory*. New York, USA: McGraw-Hill Company, 574.
- Stepanoff, A. J. (1948). *Centrifugal and Axial Flow Pumps*. New York, USA: John Wiley & Sons, 193-199.
- Stirling, T. E. (1982). *Analysis of the design of two pumps using NEL methods, Centrifugal pumps-Hydraulic design*. London, UK: Mechanical Engineering Publication Ltd, 55-73.
- Takagi, T. J., J. Kobayashi, H. Miyashiro, and H. Morimoto (1980, March). Performance prediction of single-suction centrifugal pumps of different specific speeds, In *Proceedings of the Conference on Performance Prediction of Centrifugal Pump and Compressors*, New Orleans, USA, pp. 227-234.
- Tanaka, K. and H. Ohashi (1984). Performance of centrifugal pumps at low Reynolds number (1st report, experimental study). *Trans JSME, Series B* 50(449), 279-285.
- Toyokura, T., J. Kurokawa and T. Kanemoto (1979). Performance improvement for centrifugal pump handling high viscosity oil. *Turbomachinery* 7(2), 8-15.
- Varley, F. A. (1961). Effects of impeller design and surface roughness on the performance of centrifugal pumps. *Proc Instn Mech Engrs* 175(21), 955-969.
- White, F. M. (1994). *Fluid Mechanics*. New York, USA: McGraw-Hill INC, 339-340.
- Yoon, E. S., H. W. Oh, M. K. Chung, and J. S. Ha (1998). Performance prediction of mixed-flow pumps. *Proc Instn Mech Engrs*, Part A 212, 109-115.
- Zaher, M. A. (2001). Approximate method for calculating the characteristics of a radial flow pump. *Proc Instn Mech Engrs*, Part E 215, 295-316.